

CONTENTS

Forward	iii
Table of Contents	iv
List of Figures	vii
List of Tables	x

Chapter 1: Construction Project Management 1-1

Introduction	1-1
Purpose of Construction Project Management	1-1
Agency/Contractor Relationship	1-3
TQM for HMA Construction	1-3
Sampling and Testing	1-4
Safety	1-5
Conclusion	1-5

Chapter 2: Materials 2-1

General Information	2-1
Asphalt	2-2
Aggregate	2-20

Chapter 3: Mix Design 3-1

Introduction	3-1
Mixture Characteristics and Behavior	3-1
Properties Considered in Mix Design	3-4
Evaluation and Adjustment of Mix Design	3-8
Applications of Mix Design Testing	3-11
Objectives of Mix Design	3-12
Marshall Mix Design Method	3-12
Analyzing Marshall Test Results	3-19
Hveem Mix Design Method	3-22
Superpave Mix Design	3-30

Chapter 4: Plant Operations 4-1

Purpose and Objective	4-1
General Information	4-1
Material Handling	4-3
Aggregate Drying and Heating	4-15

Emission Control Systems	4-20
Hot Mix Asphalt Storage	4-24
Quality Control and Observation of HMA Production	4-27
Safety	4-31
Batch Plants	4-32
Plant Guidelines	4-48
Drum Mix Plants	4-49

Chapter 5: Placing Hot Mix Asphalt 5-1

Objectives	5-1
Introduction	5-1
Preparation for Paving	5-3
Paving Equipment	5-14
Delivery of Hot Mix Asphalt	5-32
Placing Procedures	5-35
Inspection of Mat	5-36
Summary of Placing Procedure	5-42
Fume Recovery System	5-44

Chapter 6: Compaction 6-1

Introduction	6-1
Compaction Principles	6-1
Equipment	6-7
Rolling Procedures	6-19
Summary	6-23

Chapter 7: Quality Control and Acceptance of Hot Mix Asphalt 7-1

General	7-1
Quality Control Testing	7-5
Sampling and Testing Plan for Quality Control	7-10
Data Analysis	7-13
Acceptance Criteria	7-15
Density Specifications	7-16
Summary	7-22

Chapter 8: Segregation 8-1

Introduction 8-1
Segregation Defined 8-1
Avoiding Segregation in Production 8-6
Avoiding Segregation in Construction 8-12
Analysis of Segregation 8-16

Appendix A: Miscellaneous Tables A-1

Table A.01: Conversion Factors A-1
Table A.02: Types of Compacted Asphalt Pavements A-2
Table A.03: Composition of Asphalt Concrete A-3

Appendix B: Glossary B-1

Glossary of Terms Pertaining to Asphalt Pavement Construction B-1

Appendix C: Random Number Tables C-1

Table C.01: Random Numbers for Sampling Procedure C-2

Appendix D: AASHTO and ASTM Test Methods D-1

Table D.01: AASHTO and ASTM Test Methods as Commonly Specified D-1

Appendix E: Superpave E-1

Superpave Performance Graded Asphalt Binder Specification E-1

List of Figures

Figure 2.01	Typical Crude Oil Distillation Temperatures and Products	2-2
Figure 2.02	Typical Refining Process.	2-3
Figure 2.03	Asphalt Flow Behavior	2-5
Figure 2.04	Asphalt Behavior at Varying Temperatures	2-5
Figure 2.05	Variations of Three Viscosity-Graded Asphalts.	2-7
Figure 2.06	Penetration Test.	2-9
Figure 2.07	Capillary Tube Viscometer in Temperature-Controlled Water Bath.	2-9
Figure 2.08	Pouring Asphalt Cement Sample Into Viscometer	2-9
Figure 2.09	Flashpoint Tests.	2-10
Figure 2.10	Thin Film Oven	2-11
Figure 2.11	Rolling Thin Film Oven	2-12
Figure 2.12	Ductility Test	2-13
Figure 2.13	Pressure Aging Vessel and Components	2-14
Figure 2.14	Rotational Viscometer.	2-14
Figure 2.15	Dynamic Shear Rheometer Operation.	2-15
Figure 2.16	Bending Beam Rheometer	2-15
Figure 2.17	Direct Tension Tester	2-16
Figure 2.18	Sieve Analysis	2-30
Figure 2.19	Semi-Log Chart	2-34
Figure 2.20	0.45 Power Chart	2-35
Figure 2.21	Typical 0.45 Power Chart and Example of Grading Band	2-36
Figure 2.22	Various Types of Aggregate Specific Gravities	2-38
Figure 2.23	Los Angeles Abrasion Machine	2-38
Figure 2.24	Aggregate of Various Shapes and Surface Textures	2-39
Figure 3.01	Voids in the Mineral Aggregate (VMA) in a Compacted Mix Specimen.	3-3
Figure 3.02	Maximum Density Curves Based on FHWA 0.45 Power Gradation Chart	3-8
Figure 3.03	Determining Specific Gravity of an Aggregate Sample	3-14
Figure 3.04	Preparing Test Specimen for Marshall Mold	3-14
Figure 3.05	Marshall Drop Hammer Compacting Mix Specimen	3-16
Figure 3.06	Marshall Stability-Flow Apparatus.	3-17
Figure 3.07	Marshall Test Results: Mixture Properties vs. Asphalt Content	3-18
Figure 3.08	Saturating an Aggregate Sample with Kerosene (CKE Test).	3-24
Figure 3.09	Rodding Mixture Sample in Mold.	3-25
Figure 3.10	Mechanical Compactor Compacting Mixture Sample	3-25
Figure 3.11	Stabilometer Test	3-27
Figure 3.12	Swell Test Apparatus	3-27
Figure 3.13	Example Graphs Showing Unit Weight, Percent Air Voids And Stabilometer Values for Hveem Mixture Specimens	3-30
Figure 3.14	Pyramid Chart Used to Determine Optimum Asphalt Content	3-31
Figure 3.15	Example of Pyramid Procedures	3-31
Figure 3.16	Superpave Gradation Limits.	3-33
Figure 3.17	Superpave Gyratory Compactor and Mold Configuration	3-34
Figure 3.18	Mixture Compaction Characteristics From the Superpave Gyratory Compactor.	3-35
Figure 3.19	Air Voids, VFA and VMA vs. Asphalt Content	3-36
Figure 4.01	Batch Plant	4-2

Figure 4.02	Drum Mix Plant.	4-2
Figure 4.03	Correct and Incorrect Methods for Storing Aggregate Containing Large and Small Particles	4-4
Figure 4.04	Building a Horizontal Stockpile.	4-5
Figure 4.05	Equipment Working on Top of a Stockpile.	4-5
Figure 4.06	Aggregate Sample Reduction.	4-7
Figure 4.07	Asphalt Storage Tanks	4-8
Figure 4.08	Asphalt Return Line	4-8
Figure 4.09	Sampling Valve in Delivery Line to Mixing Chamber	4-9
Figure 4.10	Asphalt Sampling Device for Storage Tank	4-10
Figure 4.11	Silo for Feeding Mineral Filler	4-11
Figure 4.12	Aggregate Cold Feed Bins.	4-14
Figure 4.13	Typical Types of Cold Feed Systems	4-14
Figure 4.14	Typical Dryer Drum	4-16
Figure 4.15	Dryer Drum Flights and Function	4-16
Figure 4.16	Parallel Flow Dryer	4-17
Figure 4.17	Counter Flow Dryer	4-17
Figure 4.18	Types of Pryometers	4-18
Figure 4.19	Primary and Secondary dust Collectors.	4-21
Figure 4.20	Knockout Box (Primary Dust Collector)	4-22
Figure 4.21	Cyclone Dust Collector (Primary Dust Collector)	4-22
Figure 4.22	Baghouse (Secondary Dust Collector).	4-23
Figure 4.23	Wet Scrubber (Secondary Dust Collector)	4-24
Figure 4.24	Storage Silos	4-25
Figure 4.25	Surge Bin	4-25
Figure 4.26	A Batcher Above a Surge Bin	4-26
Figure 4.27	Truck Scale	4-27
Figure 4.28	Batch Plant	4-33
Figure 4.29	Screening Unit.	4-35
Figure 4.30	Screening Unit Showing Aggregate Flowing Through Screens And Into the Hot Bins	4-35
Figure 4.31	An Electronic Low Bin Indicator	4-36
Figure 4.32	Segregation of Aggregates in Each of the Hot Bins	4-37
Figure 4.33	Correct use of a Sampling Device	4-38
Figure 4.34	How Cumulative Scale Settings Are Used To Control the Amount of Aggregate Drawn From the Hot Bins	4-39
Figure 4.35	Asphalt Weighing and Delivery System in a Batch Plant.	4-40
Figure 4.36	Under-Filled Pugmill.	4-42
Figure 4.37	Over-Filled Pugmill	4-42
Figure 4.38	Pugmill “Live Zone”	4-42
Figure 4.39	Steps in a Typical Batch Plant Mixing Cycle	4-43
Figure 4.40	Automated Batch Plant Controls	4-45
Figure 4.41	Weigh Box Recycling Technique at a Batch Plant	4-46
Figure 4.42	Drum Mix Plants – Portable Type and Stationary Type	4-50
Figure 4.43	Basic Drum Mix Plant.	4-51
Figure 4.44	Cold Feed Controls	4-53
Figure 4.45	Typical Sampling Device.	4-54
Figure 4.46	In-Line Belt Weigher (Weigh Bridge)	4-54
Figure 4.47	Parallel Flow Drum Mixer	4-56

Figure 4.48	Counter Flow Drum Mixer	4-56
Figure 4.49A	Parallel Flow Drum Dryer With a Coater	4-58
Figure 4.49B	Counter Flow Dryer Drum With a Coater	4-58
Figure 4.50	Double Barrel Drum Mixer	4-59
Figure 4.51	Triple Drum Dryer/Mixer	4-59
Figure 4.52	Double Drum Dryer/Mixer	4-60
Figure 4.53	RAP Introduced Into a Drum Mix Plant	4-60
Figure 5.01	Typical Page From an Inspector's Diary	5-3
Figure 5.02	Milling Machine	5-5
Figure 5.03	Correctly Placed Leveling Wedges Ensure Smoother Pavements	5-6
Figure 5.04	Limits for Multiple-Layer Leveling Wedges Should Be Determined by Level	5-6
Figure 5.05	Correctly Placed Leveling Wedges for Overcoming Excessive Crown.	5-6
Figure 5.06	Checking Subgrade Elevations.	5-9
Figure 5.07	A Typical Asphalt Distributor	5-12
Figure 5.08	Proper Setting of Nozzles	5-13
Figure 5.09	Spray-Bar Height and Coverage.	5-13
Figure 5.10	A Typical Paver	5-16
Figure 5.11	Paver Power and Screed Units	5-16
Figure 5.12	Cedarapids Remix Paver	5-17
Figure 5.13	Self-Leveling Floating Screed	5-18
Figure 5.14	Forces Acting on the Screed	5-19
Figure 5.15	Vibratory Type Screed	5-21
Figure 5.16	Mat Thickness and Crown Controls	5-22
Figure 5.17	Automatic Screed Reference System.	5-23
Figure 5.18	Ultra Sonic Grade Sensor	5-24
Figure 5.19	Laser Grade Sensor	5-24
Figure 5.20A	Pre-Strike-Off.	5-26
Figure 5.20B	Proper Setting	5-26
Figure 5.21	Starting Blocks Under Screed	5-28
Figure 5.22	Basic Requirements for Trucks	5-29
Figure 5.23	Types of Haul Trucks	5-30
Figure 5.24	Material Transfer Vehicle.	5-31
Figure 5.25	Load Ticket	5-33
Figure 5.26	Checking Mat Thickness With a Depth Gauge.	5-40
Figure 5.27	Taking Core Sample of Pavement and Measuring Mat Thickness of Core	5-40
Figure 5.28	Bulkhead Transverse Joint and Papered Transverse Joint	5-41
Figure 5.29	Staggering Longitudinal Joints	5-43
Figure 5.30	Fume Recovery System (Courtesy of Cedarapids)	5-44
Figure 6.01	Durability Effects vs. In-place Air Voids	6-2
Figure 6.02	Forces at Work During Compaction	6-2
Figure 6.03	Time Allowed for Compaction	6-6
Figure 6.04	Static Steel-wheeled Roller	6-8
Figure 6.05	Forces Exerted on Mat by Steel-wheeled Rollers	6-8
Figure 6.06	Proper Direction of Roller Travel.	6-9
Figure 6.07	Improper Direction of Roller Travel.	6-9
Figure 6.08	Pneumatic (Rubber)-Tired Roller	6-11
Figure 6.09	Forces Exerted by Pneumatic-Tired Roller During Compaction	6-11
Figure 6.10	Single Steel-Wheeled Vibratory Roller.	6-13
Figure 6.11	Double Drum Vibratory Roller.	6-14

Figure 6.12	Illustration of Amplitude	6-14
Figure 6.13	Relationship Between Speed and Vibration Frequency	6-16
Figure 6.14	Different Modes of Vibration	6-16
Figure 6.15	Constructing a Test Strip	6-18
Figure 6.16	Rolling a Hot Longitudinal Joint	6-21
Figure 7.01	Percent Difference in Air Voids From Target Value	7-2
Figure 7.02	Percent Difference in Voids in the Mineral Aggregate From Target Value	7-2
Figure 7.03	Percent of Total Sample Variance Attributable to Factors Shown	7-5
Figure 7.04	Curing Time Influence on G_{mm} Determination	7-8
Figure 7.05	Example Excerpt From a Random Number Table	7-10
Figure 7.06	Random Sampling vs. Stratified Random Sampling a Material Lot	7-10
Figure 7.07	Typical Quality Control Charts During Mixture Production	7-14
Figure 7.08	Relationship Between Reference Density And Air Voids for 5% Air Void Mix Design	7-20
Figure 7.09	Relationship Between Reference Density And Air Voids for 4% Air Void Mix Design	7-20
Figure 7.10	Relationship Between Reference Density And Air Voids for 3% Air Void Mix Design	7-21
Figure 8.01	Segregated Hot Mix Asphalt Pavement	8-1
Figure 8.02	Typical VMA Curve	8-3
Figure 8.03	Gap-Graded Aggregate Gradation for HMA	8-4
Figure 8.04	Cone Stockpile Segregation	8-5
Figure 8.05	Cone Stockpile Built With Aggregate Ladder	8-5
Figure 8.06	Building a Stockpile Properly	8-7
Figure 8.07	Hot Bins: Minimizing Segregation in Bin No. 1	8-8
Figure 8.08	Segregation During Drum Discharge	8-9
Figure 8.09	Uniformity During Drum Discharge by Fixing a Plow at Point of Discharge	8-9
Figure 8.10	Uniformity During Drum Discharge by Turning Drag Chain 90°	8-9
Figure 8.11	Fine Aggregate Segregation of HMA on the Roadway	8-10
Figure 8.12	Plant Modifications to Avoid Segregation	8-10
Figure 8.13	Improper and Proper Methods of Loading Trucks With HMA	8-13
Figure 8.14	Chevron-Shaped Segregation on the Roadway	8-14
Figure 8.15	Material Which Segregated Before Mixing	8-17
Figure 8.16	Material That Segregated After Mixing	8-17

List of Tables

Table 2.01	Guideline Temperatures for Storing Asphalts	2-18
Table 2.02	Guide for Loading Asphalt Products	2-19
Table 2.03	Temperature-Volume Corrections for Asphalt	2-21
Table 2.04	Aggregate Classifications	2-25
Table 2.05	Typical Composition of Hot Mix Asphalt	2-31
Table 2.06	Typical Sieve Sizes	2-32
Table 2.07	Sieve Analysis Data Converted to Aggregate Gradation	2-32
Table 3.01	Causes and Effects of Pavement Instability	3-5
Table 3.02	Causes and Effects of Lack of Durability	3-5

Table 3.03	Causes and Effects of Permeability	3-6
Table 3.04	Causes and Effects of Workability Problems	3-7
Table 3.05	Causes and Effects of Poor Fatigue Resistance	3-7
Table 3.06	Causes and Effects of Poor Skid Resistance	3-8
Table 3.07	Marshall Mix Design Criteria	3-20
Table 3.08	Minimum VMA Requirements	3-21
Table 3.09	Surface Area Factors	3-24
Table 3.10	Example of Calculation of Surface Area	3-24
Table 3.11	Suggested Test Report Form Showing Test Data For a Typical Mix Design by the Hveem Method.	3-29
Table 3.12	Hveem Mix Design Criteria	3-30
Table 4.01	Size of Samples Adequate for Routine Grading And Quality Analysis per AASHTO T2	4-6
Table 4.02	Possible Causes of Deficiencies in Hot Mix Asphalt	4-29
Table 5.01	Spraying Temperature Range for Prime and Tack Coat.	5-15
Table 5.02	Typical Problems and Their Probable Cause	5-38
Table 6.01	Guide for Setting Vibratory Compactor Controls In Relation to Layer Thickness.	6-17
Table 6.02	Factors Influencing Compaction.	6-22
Table 7.01	Mix Design Verification Results by Mix Number and Designer	7-3
Table 7.02	Sample Quality Control and Acceptance Procedures	7-4

A

American Association of State Highway and Transportation Officials, standards of

- AASHTO M 20, 2-8
- AASHTO M 92, 3-21
- AASHTO M 226, 2-8
- AASHTO MP 1, 2-8, 3-32
- AASHTO T 11, 2-33
- AASHTO T 27, 2-33
- AASHTO T 40, 4-10
- AASHTO T 209, 3-18, 3-26
- AASHTO T 166, 3-16
- AASHTO T 176, 2-37
- AASHTO T 245, 3-13
- AASHTO T 246 and T 247, 3-22
- AASHTO T 248, 4-7
- AASHTO T 283, 2-40, 3-37
- AASHTO T 304, 2-39
- AASHTO T 84 and T 85, 3-15, 3-23
- AASHTO T 96, 2-39

Absorption, 2-39

Aggregate, 2-20

- classification of, 2-20
- cold feed, 4-13
- consensus properties, 3-32
- drying and heating, 4-15
- gradation, 2-31
- handling and sampling of, 2-28, 4-3, 4-6
- moisture check, 4-20
- natural, 2-26
- processed, 2-26
- synthetic, 2-27
- production of, 2-27
- properties of, 2-29
- source properties, 3-32
- sources, 2-26
- stockpiling of, 2-27, 4-3
- storage of, 4-3
- surface capacity, 3-23
- temperature control, 4-19
- thru, 4-9

Asphalt, 2-1, 2-2

- behavior, 2-4
- classification of, 2-6
- handling hot, 2-17
- plant, 4-1
- refining, 2-3, 2-4
- storing of, 2-16, 4-7
- sampling of, 2-19, 4-10
- specifications, 2-8

American Society for Testing and Materials, standards of

- ASTM C 117, 2-33
- ASTM C 127 and C 128, 3-15, 3-23
- ASTM C 131 or C 535, 2-39
- ASTM C 136, 2-33
- ASTM C 140, 4-10
- ASTM C 702, 4-7
- ASTM D 1559, 3-13
- ASTM D 1560 and D 1561, 3-22
- ASTM D 2041, 3-18, 3-26
- ASTM D 2419, 2-37
- ASTM D 2726 or D 1188, 3-16
- ASTM D 3381, 2-8
- ASTM D 3665, 4-7
- ASTM D 5821, 2-39
- ASTM D 946, 2-8
- ASTM E 11, 3-21

B

Bag houses, 4-23

Base course, 5-4

Batch plants, 4-32

- calibration, 4-38
- pugmill mixing, 4-41
- automation, 4-43
- recycling techniques, 4-44

Bending Beam Rheometer, 2-16

C**Capillary tube viscometer,**
2-9**Clay content,** 2-37**Compaction,** 6-1breakdown, 6-23
cold weather, 6-5
factors affecting, 6-3, 6-22
finish, 6-23
intermediate, 6-23
joints, 6-20
mechanics of, 6-1
rolling requirements, 6-17
thin lifts, 6-19
thick lifts, 6-20
vibratory rollers, 6-15**Construction Project
Management,** 1-1**Contract,** 1-2**Control strip density,**
6-18, 7-18**Counter flow dryer,** 4-17**Cracking and seating
(breaking and seating),**
5-7**Cyclone Dust Collector,**
4-21, 4-22**D****Density analysis,** 3-19**Design aggregate
structure,** 3-33**Direct Tension Tester,**
2-16**Distillation,** 2-2**Distributor controls,** 5-12**Distributor,** 5-11**Drum mix plants,** 4-2, 4-49
counter flow, 4-57
coater unit, 4-57
double barrel, 4-57
double drum, 4-59history, 4-49
operations, 4-51, 4-55
parallel flow, 4-56
recycling, 4-61
triple drum, 4-58**Ductility,** 2-12**Durability,** 3-4**Dust Collection,** 4-21, 4-23
scrubber, 4-23**Dynamic Shear****Rheometer,** 2-14**E****Elastic,** 2-5**Emission control system,**
4-20**F****Fatigue resistance,** 3-7**Flashpoint,** 2-10**Flow Test,** 3-16**Fume recovery system,**
5-44**G****Grading charts (semi-log
chart, 0.45 power chart),**
2-34, 2-35, 2-36**Grading**aggregate, 2-31
asphalt, 2-8**H****Handwork,** 5-36**Haul trucks,** 5-28**HMA overlay,** 5-4**HMA production,** 4-27
quality control, 4-27
safety, 4-31**Horizontal and vertical
grade control,** 5-8
profile grade line (PGL),
5-8**Hveem Mix Design,** 3-22
Centrifuge Kerosene
Equivalent (CKE), 3-23
K factor, 3-24
Stabilometer Test, 3-26
Swell Test, 3-26
analysis of, 3-28**I****Impermeability,** 3-5**Inspection of mat,** 5-32**J****Job mix formula,** 3-11
verification, 7-13**Joints,** 5-39
cold, 5-42
hot, 5-42
longitudinal, 5-42
transverse, 5-39**K****Knockout box,** 4-21**L****Laboratory density,** 7-17**Leveling wedges,** 5-5**Load tickets,** 5-32
through, 5-34**Long term aging,** 2-6

Low temperature cracking, 2-6

M

Marshall Mix Design, 3-12

Maximum particle size, 2-29

Maximum theoretical density, 7-17

Method density specification, 7-18

Mineral filler, 2-33, 3-3
storage and handling of, 4-5, 4-11

Mix evaluation, 3-8

Mixture, density of, 3-1
air voids, 3-2
VMA, 3-2
VFA, asphalt content, 3-2

Moisture susceptibility, 2-40
sensitivity, 3-35

N

Nominal maximum particle size, 2-29

Nuclear density gauge, 6-18, 7-18

O

Oxidation, 2-6

Oxidative hardening, 2-6
(see age hardening), 2-6

P

Parallel flow dryer, 4-17

Particle shape, 2-39

Pavement geometrics, 5-39

Pavement lane crown, 5-39

Pavers, 5-15
tractor unit, 5-15
tires or tracks, 5-15
hopper, flow gates, auger, 5-17
hopper feeder augers, 5-17
screed unit, 5-19
tamping bar types, 5-21
screed controls, 5-22
control systems, 5-27
calculating yield, 5-34

Penetration, 2-8

Performance grading, 2-8

Placement of HMA, 5-35
summary of, 5-43

Plans, 1-2

Plastic, 2-4

Preliminary design testing, 3-11

Pressure aging vessel, 2-13

Primary collectors, 4-21

Prime coats, 5-9

Q

Quality assurance/Quality control, (QA/QC),

1-3
acceptance plans, 7-15
air voids, 7-9
asphalt content, 7-6
aggregate gradation, 7-6
bulk specific gravity, 7-8
maximum specific gravity, 7-8
QC testing, 7-13

R

Reclaimed Asphalt Pavement (RAP), 4-44

Reference density specification, 7-19

Restricted zone, 3-33

Rollers, 6-7
amplitude, 6-15
frequency, 6-15
static steel-wheel tandem, 6-7
pneumatic-tired, 6-10
vibratory, 6-12
rolling requirements, 6-17
summary, 6-23

Rolling Thin Film Oven, 2-11, 2-14

Rotational (Brookfield) Viscometer, 2-14

Rubblization, 5-7

S

Secondary collectors, 4-23

Segregation, 8-1
discharge systems, 8-12
from handling and stockpiling, 8-6
flow gates, 8-15
in mix design, 8-3
trouble spots, 8-2
of cold bins, 8-7
of hot bins, 8-7
of drum mixer, 8-8
of hot elevator, 8-8
overview, 8-1
pinpointing, 8-16
paver, 8-13
pugmill and surge gates, 8-11
surge and storage bins, 8-11
severity, 8-19
truck loading, 8-12
types, 8-2

Skid resistance, 3-8
Solubility Test, 2-12
Source acceptance testing, 3-11
Specific gravity, 2-12, 2-37
Specifications, 1-2
Spray bar, 5-11
Stability Test, 3-16
Stability, 3-10
Standard specifications, 1-2
Storage silos, 4-29
Subgrade, 5-3
Superpave, 2-13
 design asphalt content, 3-35
 design aggregate structure, 3-33
 gyratory compactor, 3-34
 selection of materials, 3-32
 moisture sensitivity, 3-35
 mix design system 3-30
Surge bins, 4-14

T

Tack coats, 5-10
Thin Film Oven, 2-11
Total Quality Management (TQM), 1-3
Toughness, 2-37

U

Undersealing, 5-7

V

VFA analysis, 3-18, 3-19
Viscoelastic, 2-4
Viscosity, 2-8
Viscosity after aging, 2-10
VMA analysis, 3-18

Voids analysis, 3-17
Visual Inspection, 5-32

W

Washed-sieve analysis, 3-15
Wet scrubber, 4-23
Workability, 3-6